

Boone County 2019 One-and-Six-Year Plan

One Year Projects and Locations:

C-6(386): Replacement of an under 20' bridge with a CBC, T20N, R7W, NE qtr of Sec. 28 and NW qtr of Sec. 27; 190th Ave., north of 270th St.; \$70,000

C-6(391): Bridge 6(23445); tear out existing structure and replace with a CBC; T20N, R5W, between Sections 24 & 25; 260th St. east of 330th Ave.; \$70,000

C-6(393): Bridge 6(11215); remove existing bridge and install a CBC; T22N, R5W, between Sections 25 & 36; 150th St. east of 330th Ave.; \$160,000

C-6(394): Road Resurfacing; milling, resurfacing, shoulder work; T22N, R7W, Sections 26, 27, 28, 29; 145th St., 4 miles going west from 210th Ave. to 170th Ave.; \$3.6 million

C-6(395): Road improvement; dig ditch, build up road to increase drainage, remove trees; T19N, T18N, R8W, between Sections 33 & 4; 340th St. for ¾ mile going west from 130th Ave.; \$5,000

C-6(397): Culvert structure; tear out existing structure and replace with CBC; T19N, R7W, between Sections 17 & 20; 310th St. east of 175th Ave. ¼ mile.; \$70,000

C-6(398): Bridge 6(23340); tear out existing structure and replace CBC; T22N, R6W, Sections 10SE and 11SW; 260th Avenue, ¼ mile North of 120th Street; \$70,000

C-6(400): Ditch work; install culverts in driveways, fix drainage issues; T19N, R8W, Sections 10S and 15N; 300th Street between 130th Avenue and 140th Avenue, in the middle for ½ mile; \$15,000

C-6(402): Road lower than ditches; need to dig ditches, build up road and add culverts; T20N, R8W, Sections SE qtr. 25 and NE qtr. 36; 270th Street going west for ¼ mile off 160th Avenue; \$25,000

Six Year Projects and Locations:

C-6(359): Bridge 6(00830); replace wooden structure with twin barrel CBC; T22N, R5W, between the SW qtr. Section 14 and the NW qtr. Section 23; 130th St.; \$90,000

C-6(366): Road improvement, rebuild road & ditch work; T18N, R7W, beginning at the NW corner of Section 27 and the NE corner of Section 28, going for 1 mile; 190th Ave.; \$20,000

C-6(390): Bridge 6(11815); replace wooden deck with pre-cast slab deck with W-Channel guard rails; T21N, R6W, NW qtr of Section 11 and NE qtr of Section 10; 180th St. east of 260th Ave.; \$80,000

C-6(392): 260th St. & Hwy 14 intersection,(Cargill Road); redo the intersection; T20N, R6W, beginning at Hwy 390 & Hwy 14, go east 0.43 miles along the NE qtr of Section 27 and the SE qtr of Section 22; 260th St.; \$308,000

C-6(399): Cattle pass, tear out existing cattle pass and replace with a new small CBC single barrel cattle pass; T21N, R5W, Sec 7SE; 180th Street, 2/3 mile west of 290th Avenue; \$60,000

C-6(401): Culvert structure; remove existing culvert structure and replace with a 40ft. bridge; T18N, R5W, Sections 10SE and 11SW; 320th Avenue, from 350th Street going south to the ½ mile line; \$350,000